




NOTES

1. WOOD OFFSET BLOCKS 8 x 6x 14 INCHES TO BE USED ON ALL NEW CONSTRUCTION AND WHEN THE EXISTING TRAFFIC BARRIER WITH METAL OFFSET BLOCKS IS TO BE REMOVED AND RESET.
2. THE CONTRACTOR HAS THE OPTION TO USE SHORTER BOLTS WITH A MINIMUM OF 1/2" PROTRUSION BEYOND NUT.
3. WOOD BLOCKS FOR THRIE BEAM PANELS SHALL BE 8x6x22 1/2 INCHES AND NOTCHED AS SHOWN IN THE TOP VIEW. TWO BOLTS ARE REQUIRED FOR ATTACHMENT TO THE POSTS.
4. THE 6 x 6x 14 INCH WOOD OFFSET BLOCKS ARE TO BE USED FOR REPAIR WORK ONLY.

	APPROVED:  DEPUTY DIRECTOR - OPERATIONS  DIRECTOR, DEPARTMENT OF TRANSPORTATION	CITY OF BALTIMORE DEPARTMENT OF TRANSPORTATION TRAFFIC DIVISION	ISSUED 8 / 2010	REVISED	REVISED
	TRAFFIC BARRIER W BEAM WITH WOOD OFFSET BLOCK			STANDARD NO. BC 660.04	
			SCALE : NONE	SHEET 1 OF 1	