



MINIMUM NUMBER OF SPANS = 2
 MINIMUM NUMBER OF POSTS = 3
 MAXIMUM SPAN: 12'-6"
 LENGTH OF BARRICADE NOTED ON PLANS:
 CENTER TO CENTER OF END POSTS.
 ALL SPANS TO BE EQUAL LENGTH.
 NO. OF POSTS TO BE NOTED ON PLANS.
 ALL POSTS W6 x 8.5, 5'-9" LONG
 SEE BC 660.02

TRAFFIC BARRIER W BEAM BARRICADE SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER LINEAR FOOT. THE CONTRACT PRICE BID SHALL INCLUDE THE FURNISHING AND INSTALLATION OF ALL POSTS, W BEAM, POST AND SPLICE BOLTS WITH NUTS, END SECTIONS, GALVANIZING, THE COST OF ALL EXCAVATION, BACKFILLING AND TAMPING INCIDENTAL TO SETTING THE POSTS, OR THE COST OF DRIVING THE POSTS, THE COST OF THE REMOVAL OF EXISTING PAVEMENT WHERE NECESSARY, AS WELL AS THE COST OF ALL LABOR, APPROVED TOOLS AND EQUIPMENT INCIDENTAL TO FURNISHING AND INSTALLING THE BARRICADE AT LOCATIONS NOTED ON THE PLANS OR WHERE DIRECTED BY THE ENGINEER. FOR MATERIAL, SEE THE LATEST DEPARTMENT OF GENERAL SERVICES SPECIFICATIONS FOR TRAFFIC BARRIER W BEAM.



APPROVED:
Frank Murphy
 DEPUTY DIRECTOR - OPERATIONS
Khalil Zane
 DIRECTOR, DEPARTMENT OF TRANSPORTATION

CITY OF BALTIMORE
 DEPARTMENT OF TRANSPORTATION
 TRAFFIC DIVISION
 TRAFFIC BARRIER W BEAM BARRICADE

ISSUED	REVISED	REVISED
8 / 2010		
STANDARD NO. BC 660.61		
SCALE: NONE	SHEET 1 OF 1	